BREAKDOWN OF DETAILED ESTIMATE

PROJECT NAME:		COMPLETION OF HOSTEL (FUNCTION/BUSINESS CENTER) INTERNATIONAL HOUSE										
LOCATION:		CatSU Main Campus, Virac, Catanduanes										
TEM N	•	VII										
ITEM No. DESCRIPTION: TOTAL QUANTITY: UNIT:		XII REINFORCING STEEL (DEFORMED) 66389.29										
							mai.		kgs.			
	16. WATER	TANK SADDLE, 3000 PSI	1									
		Ø X 6.0M RSB Grade 40	kgs	59.66								
		m Ø X 6.0M RSB Grade 40	kgs	201.34								
	10-10mr	10-10mm Ø X 6.0M RSB Grade 40		38.84								
	# 16 G.I	. Tie Wire	kgs kgs	6.00								
			, ngo	0.00								
				Sub-Total for C (Material Cost)								
D	Direct Unit Cost		(A + B + C)									
Ε	Overhead, Contingencies & Misc. (OCM)		% of D									
F			% of D									
Н	ITEM TOTA	L		(D+E+F+G)								
T	TOTAL UNI	T COST		(H / Total Qty)								
				(117 Total Giy)								
		Signature		in the capacity	/ of							
				,								
	Duly author	ized to sign the Bid and on behalf of										



LOGO HERE

CONTRACTOR'S LETTERHEAD HERE

BREAKDOWN OF DETAILED ESTIMATE

PROJECT NAME:

COMPLETION OF HOSTEL (FUNCTION/BUSINESS CENTER) INTERNATIONAL HOUSE

LOCATION:

CatSU Main Campus, Virac, Catanduanes

ITEM No.

XIII

DESCRIPTION:

UNINSTALLED REINFORCING STEEL (DEFORMED) - DEDUCTIVE

TOTAL QUANTITY:

8908.99

UNIT:

cu.m

Α.	LABOR	No. of Person	No. of Days	Daily Rate	Amount
		Sub	-Total for A (Cost of Labor)	-

В.	EQUIPMENT	No. of Units	No. of Hours	Hourly Rate	Amount
		Sub-Total for B (Cost of Equ	ipment Rental)	

_	Name and Specification	Unit		Unit Cost	Amount
C.	Materials		Quantity		
	LIST OF NOT INSTALLED REBARS STORED @ PROJECT SITE				
	156-20mm Ø X 9.0M RSB Grade 40	kgs	3462.26		The second secon
	127-16mm Ø X 10.50M RSB Grade 40	kgs	2104.58		
	72-20mm Ø X 2.2M RSB Grade 40 (Assembled footing for genset = 4 sets)	kgs	390.61		
	23-25mm Ø X 3.80M RSB Grade 40 (Bended bars for elevator foundation)	kgs	336.76		
	35-25mm Ø X 4.40M RSB Grade 40 (Bended bars for elevator foundation)	kgs	593.38		
	160-12mm Ø X 1.350M RSB Grade 40 (Stirrups for genset columns)	kgs	191.76		
	300-12mm Ø X 1.350M RSB Grade 40 (Stirrups for genset beams)	kgs	359.54		
	106-16mm Ø X 2.40M RSB Grade 40 (horizontal bar for elevator core)	kgs	401.50		
	41-12mm Ø X 10.00M RSB Grade 40 (slab rebars @ roof deck)	kgs	363.98		
	27-12mm Ø X 8.00M RSB Grade 40 (slab rebars @ roof deck)	kgs	191.76		
	25-12mm Ø X 7.00M RSB Grade 40 (slab rebars @ roof deck)	kgs	155.36		
	31-12mm Ø X 1.50M RSB Grade 40 (slab rebars @ roof deck)	kgs	41.28		
	39-12mm Ø X 1.90M RSB Grade 40 (slab rebars @ roof deck)	kgs	65.78		
	40-12mm Ø X 2.40M RSB Grade 40 (slab rebars @ roof deck)	kgs	85.22		
	26-12mm Ø X 3.00M RSB Grade 40 (slab rebars @ roof deck)	kgs	69.25		MOREON STORMAN MARK SHAREST ENGINEERS OF THE PARK A TO SHARE A TO
	47-12mm Ø X 2.30M RSB Grade 40 (slab rebars @ roof deck)	kgs	95.97		
	Sub-Total for C (Material Cost)	L			
D	Direct Unit Cost (A + B + C)			-	
E	Overhead, Contingencies & Misc. (OCM)% of D				
F	Contractor's Profit	Contractor's Profit% of D			
G	VAT		% (D + E	+F)	
Н	ITEM TOTAL		(D+E+F+	G)	

I TOTAL UNIT COST	(H / Total Qty)	

50

BREAKDOWN OF DETAILED ESTIMATE

PROJECT NAME:	COMPLETION OF HOSTEL (FUNCTION/BUSINESS CENTER) INTERNATIONAL HOUSE				
LOCATION:	CatSU Main Campus, Virac, Catanduanes				
ITEM No.	XIII				
DESCRIPTION:	UNINSTALLED REINFORCING STEEL (DEFORMED) - DEDUCTIVE				
TOTAL QUANTITY:	8908.99				
UNIT:	cu.m				
Signature	in the capacity of				
Duly autho	rized to sign the Rid and on hehalf of				

